



Holland Township Community Pool



2022

ABOUT THIS PROJECT:

Market Segment:
General Construction

Contractor:
RFS Commercial

Products Used:
Xypex Concentrate
Xypex Patch'n Plug
Xypex Megamix II

Location:
Milford, NJ

Owner:
Holland Township

DESCRIPTION

The Holland Township Community Pool in Milford, NJ, has existed since the 1950s. However, deterioration over time has resulted in severe cracks in the concrete. The cracks have compromised the pool's ability to maintain a watertight structure, necessitating annual repairs.

Given the impending start of the pool season, timing was paramount. RFS Commercial, the appointed contractor, strategically opted for Xypex Patch'n Plug, supplemented with Concentrate, to seal the cracks and expedite painting operations swiftly.



THE XYPEX SOLUTION

The repair process entailed carefully chasing cracks, followed by the application of Patch'n Plug and then applying Xypex Concentrate complete the restoration. In areas with substantial damage to the walls, Concentrate and Megamix II were both utilized to restore the surface.

Utilizing Xypex for the repairs was pivotal in minimizing the pool's downtime, resulting in its swift return to operation just five days after repairs were completed. A Xypex sales representative on-site proved invaluable, offering assistance in problem diagnosis and ensuring the seamless execution of the repair process.



This collaborative effort not only saved time but also significantly reduced the pool's downtime, perfectly aligning with RFS Commercial's objective of delivering superior results to their clientele.

By leveraging Xypex's comprehensive repair system, RFS Commercial effectively addressed the structural issues plaguing the Holland Township Community Pool. The seamless execution of repairs underscores the efficacy of Xypex's products in delivering durable, cost-effective solutions, thereby fulfilling the client's requirements with excellence.

